
2 This Mitigated Negative Declaration (MND) has been prepared by the California State 3 Lands Commission (CSLC), as lead agency under the California Environmental Quality 4 Act (CEQA) (Pub. Resources Code, § 21000 et seq.) in order to analyze and disclose 5 the potential environmental effects associated with the ExxonMobil Production 6 Company (ExxonMobil or Applicant) Santa Ynez Unit (SYU) Offshore Power System 7 Reliability-B Phase 2 Project (OPSR-B or Project). The proposed Project includes the 8 installation and operation of replacement cables and electrical systems from the Las 9 Flores Canyon Processing Facility (LFCPF) in Santa Barbara County to Outer 10 Continental Shelf (OCS) Platforms Harmony and Heritage, and the retrieval of existing 11 out-of-service cables from selected locations within the Project area (Figures ES-1 and 12 ES-2). The CSLC would need to amend existing State Lease PRC 7163.1, a General 13 Lease - Right-of-Way Use, to allow for Project implementation. This MND establishes 14 the current environmental and regulatory setting, provides an analysis of Project-15 specific impacts, and includes recommended mitigation measures to reduce potential 16 impacts of the Project to a less than significant level.

ES.1 PROPOSED PROJECT

- 18 The OPSR-B has been divided into two phases: Phase 1, which has received its
- 19 approvals and is currently ongoing (anticipated to be completed in April 2015); and
- 20 Phase 2, which is analyzed in this MND.
- 21 Phase 1 is referred to in this MND as preparatory work required prior to Phase 2
- 22 activities. It occurs exclusively in Federal waters and involves modifications at Platforms
- 23 Harmony and Heritage for the replacement cables and electrical systems required for
- 24 Phase 2 installation. As lead agency for the Phase 1 Project, the Bureau of Safety and
- 25 Environmental Enforcement (BSEE): (1) prepared an Environmental Assessment (EA),
- 26 which concluded that no significant impacts are anticipated as a result of Phase 1
- 27 activities; and (2) issued, on April 18, 2013, a Finding of No Significant Impact (FONSI)
- 28 for the Phase 1 Project.
- 29 Phase 2 involves the retrieval of existing Cables A (or B) and C1 from selected locations
- and installation of replacement Cables A2 (or B2), F2 and G2 (Table ES-1). The Project
- 31 will use a primary cable installation vessel (CIV), which will be dynamically positioned
- will use a primary casic installation vessel (Grv), which will be dynamically positioned
- 32 and will not require the use of anchors. Several contingency scenarios have been
- 33 included in case one of the existing out-of-service cables cannot be removed from, or a
- replacement cable cannot be installed into, a conduit or platform riser (i.e., Cable F2 at
- nearshore conduit, Cable G2 at Platform Heritage riser, Cable A2 (or B2) at nearshore
- 36 conduit and at Platform Harmony riser). The decision on whether Cable A or B will be
- 37 replaced will be based on a detailed analysis of the condition of each cable prior to
- 38 installation.



Figure ES-1. Project Location



Red Cables A2 (or B2), F2 & G2 will be installed replacement cables. Blue Cables B (or A), D, D1, & E are existing cables that will remain in operation. Black dashed Cables A (or B), C1 & C will be abandoned in place. Cables A (or B) & C1 will be retrieved in tunnel, conduits, State waters and adjacent to platforms.

Figure ES-2. Proposed Project Components

Cable **Cable Route Status** ORIGINAL/EXISTING Between LFCPF and Platform Harmony* Original Α В Between LFCPF and Platform Harmony Original; repaired in 2013 Between LFCPF and Platform Heritage* Original; replaced in 2003 with Cable C1 C1 Replaced Cable C in 2003: Between LFCPF and Platform Heritage subsequently repaired twice D Between Platforms Harmony and Hondo Original D1 Between Platforms Harmony and Hondo Installed in 2003 to improve reliability E Between Platforms Harmony and Heritage Original **PROPOSED** A2 or B2 Between LFCPF and Platform Harmony F2 Between LFCPF and Platform Harmony Between Platforms Harmony and Heritage (Federal waters only) G2

Table ES-1. Project Components

- 1 Phase 2 would require the following primary components:
 - Pre-Project preparation activities: Pre-retrieval/removal surveys soil, marine, biological, and anchor locations; Installation aids and kelp cutting.
 - Vessel mobilization.
 - Retrieval of out-of-service cable at LFCPF (onshore) and offshore locations.
 - Prepare the onshore area, tunnel, and nearshore conduits to retrieve Cable C1 and Cable A [or B] from an onshore point at the southern end of the LFCPF to just beyond the State-Federal jurisdictional boundary (approximately at the OCS break).
 - Retrieve approximately 10.6 miles (17.1 kilometer [km]) of Cable C1 and A (or B). This includes removal of existing concrete blocks where the Project right-of-way crosses the Pacific Offshore Pipeline Company (POPCO) gas pipeline (POPCO crossing).
 - Retrieve a 1- to 6-mile-long (1.6 to 9.6 km) section of Cable A (or B) at and adjacent to Platform Harmony. Due to the restricted route available for installing the replacement cable, an additional section of Cable A (or B) may have to be retrieved from the State-Federal boundary to the platform.
 - Retrieve 1 to 2 miles (1.6 to 3.2 km) of Cable C1 at, and adjacent to, Platform Heritage.

18

19

2

3

4

5

6

7

8

July 2014

^{*} Water depths at Platforms Harmony and Heritage are 1,198 feet and 1,075 feet, respectively.

- Cable replacement at LFCPF (onshore) and offshore locations.
 - Install approximately 10.6 miles (17.1 km) of replacement Cable A2 (or B2) between Platform Harmony and the southern end of the LFCPF. This includes placement of concrete blocks or articulated concrete mats at the POPCO crossing.
 - Install approximately 11.3 miles (18.2 km) of replacement Cable F2 between Platform Harmony and the southern end of the LFCPF. This includes the placement of concrete blocks or articulated concrete mats at the POPCO crossing area.
 - Install approximately 8.1 miles (13.0 km) of replacement Cable G2 between Platform Harmony and Platform Heritage.
 - Cable execution contingencies (if necessary).
 - Testing and energization of the cables.

3

4

5

6

7

8

9

10

11

12

13

- Post-installation marine biological survey.
- 15 ExxonMobil estimates that the Project will require approximately 8 to 12 months to
- 16 complete. The Phase 2 onshore cable retrieval and installation activities are expected to
- 17 commence in or about the fourth quarter of 2014 and be completed by about early
- 18 fourth guarter 2015. The offshore cable retrieval and installation portion of Phase 2 is
- 19 expected to require 1 to 2 months and be conducted during mid to late 2015.

ES.2 BACKGROUND/EXISTING CONDITIONS

- 20 As part of the SYU Expansion Project in the early 1990s, Platforms Harmony, Heritage,
- 21 and Hondo were required to use shore-based electric power. As such, the electrical
- 22 power distribution systems for the platforms were installed. The systems consisted of an
- 23 Offshore Substation (OSS) located at the LFCPF and three power cables from the
- 24 substation going offshore; two to Platform Harmony (Cables A and B) and one to
- 25 Platform Heritage (Cable C). In addition, power cables were installed from Platform
- 26 Harmony to Platform Hondo (Cable D) and to Platform Heritage (Cable E). The
- 27 installation also included the associated electrical equipment at each facility. Once the
- 28 electrical distribution system was energized, the SYU offshore operations became
- 29 completely reliant on these systems for all normal operations.
- 30 In 1999, Cable C experienced a failure in State waters that could not be repaired. The
- 31 SYU Offshore Power System Repair-A Project (OPSR-A) replaced Cable C with Cable
- 32 C1 in 2003 and installed Cable D1 between Platforms Harmony and Hondo to improve
- reliability. Since Cable C1 was installed, the cable has failed, and was repaired and
- returned to service, twice. In May 2013, Cable B failed at a splice in the onshore section
- of that cable near the southern end of the LFCPF. After approvals were received from

- 1 Santa Barbara County (SBC) in June 2013, the failed section of Cable B was removed
- 2 and a section of spare cable was spliced into the existing cable. The repaired Cable B
- 3 was tested and returned to service in July 2013.
- 4 The reliability of the current offshore power distribution system requires improvement
- 5 due to aging of existing individual circuits, history of submarine cable faults in the
- 6 distribution system, and the obsolescence of offshore switchgear and electrical
- 7 components. The Project will improve the reliability of electricity distribution from shore
- 8 to, and between, the platforms.

11

12

13

14

15

16

17

18

19

- 9 CSLC actions that relate to Lease No. PRC 7163.1 and the Project are as follows.
 - On January 21, 1988, the CSLC authorized the issuance of a General Lease —
 Right-of-Way Use to Exxon Corporation (now known as the ExxonMobil
 Production Company) for a crude oil/water emulsion pipeline, a treated water
 outfall line and three power cables (A, B and C) associated with the SYU in the
 Santa Barbara Channel.
 - On February 21, 2003, the CSLC authorized an amendment to the Lease for the removal of the failed Cable C and installation of Cable C1 within State waters.
 - On August 30, 2013, ExxonMobil submitted an application to the CSLC requesting an amendment to the existing lease to allow for Project implementation.

20 ES.3 PUBLIC REVIEW AND COMMENT

- 21 Pursuant to State CEQA Guidelines sections 15072 and 15073, a lead agency must
- 22 issue an MND in draft form for a minimum 30-day public review period. Agencies and
- 23 the public will have the opportunity to review and comment on the draft document.
- 24 Responses to written comments received by the CSLC during the public review period
- 25 will be incorporated into the Final MND. In accordance with State CEQA Guidelines
- section 15074, subdivision (b), the CSLC will review and consider the proposed Final
- 27 MND, together with any comments received during the public review process, prior to
- 28 taking action on the MND and Project.

29 ES.4 ENVIRONMENTAL IMPACTS AND PROPOSED MITIGATION MEASURES

- 30 Table ES-2 provides a summary of environmental resource areas that would have the
- 31 potential to be affected by the proposed Phase 2 Project. Table ES-3 provides a list of
- 32 Mitigation Measures incorporated into the Project to reduce or avoid potentially
- 33 significant impacts as further described within Section 5.0, Mitigation Monitoring
- 34 Program. As discussed further in Section 3.0 (Environmental Analysis and Checklist),
- with implementation of the proposed Mitigation Measures, all Project-related impacts
- 36 would be reduced to less than significant.

Table ES-2. Environmental Issues and Potentially Significant Impacts

| | Agriculture and Forest Resources | Air Quality | |
|--|------------------------------------|---------------------|--|
| Biological Resources (Terrestrial and Marine) | Cultural Resources | ☐ Geology and Soils | |
| ☐ Greenhouse Gas Emissions | Hazards and Hazardous Materials | | |
| □ Land Use and Planning | ☐ Mineral Resources | ☐ Noise | |
| ☐ Population and Housing | ☐ Public Services | □ Recreation | |
| | □ Utilities and Service Systems | | |
| Mandatory Findings of Significance | | | |
| ☐ Other Major Areas of Concern: Commercial Fishing and Environmental Justice | | | |

Table ES-3. Summary of Proposed Project Mitigation Measures/Applicant Proposed Measures (MMs/APMs)

| Aesthetics | | |
|--------------------------------------|---|--|
| MM VIS-1: | Glare Minimization | |
| Air Quality/Greenhouse Gas Emissions | | |
| MM AQ-1: | Emissions Reporting Plan | |
| MM AQ-2: | Low-Sulfur Fuels | |
| MM AQ-3: | Construction Emissions Reduction | |
| MM AQ-4: | Dust Control Measures | |
| Biological Res | sources | |
| MM TBIO-1: | Terrestrial Wildlife Awareness Training | |
| MM TBIO-2: | Breeding/Nesting Bird Protection | |
| MM MBIO-1a: | Pre-Construction Marine Biological Survey | |
| MM MBIO-1b: | Anchoring Plan | |
| MM MBIO-2: | Site Access | |
| MM MBIO-3a: | Cable Installation and Retrieval | |
| MM MBIO-3b: | Post-Project Survey | |
| MM MBIO-3c: | Post-Project Technical Report | |
| MM MBIO-4: | Excavated Sand Disposal (Conduit) | |
| MM MBIO-5: | Abalone Avoidance | |
| MM MBIO-6: | Marine Wildlife Monitoring and Contingency Plan (MWMCP) | |
| MM MBIO-7: | Offshore Vessel Lighting | |
| Cultural and P | aleontological Resources | |
| MM CUL-1: | Avoidance of Offshore Cultural Resources. | |
| MM CUL-2: | Avoidance of Onshore Cultural Resources. | |
| Geology and S | Soils | |

| MM GEO-1: | Engineering Design |
|-----------------|---|
| Hazards and F | łazardous Materials |
| MM HAZ-1: | Use and Storage of Lubricating Oils, Hydraulic Fluids, and Waste Oils |
| MM HAZ-2: | Loading of Project Materials |
| MM HAZ-3: | Fueling Measure |
| MM HAZ-4: | Anchor Setback |
| MM HAZ-5: | Critical Operations and Curtailment Plan (COCP) |
| MM HAZ-6: | Cable Release Prevention Plan |
| MM HAZ-7: | Oil Spill Response Plan (OSRP) |
| MM HAZ-8: | Oil Spill Response Plan (OSRP) Training |
| MM HAZ-9: | Safety Plan for Tunnel Cable Installation and Removal Operations |
| MM HAZ-10: | Execution Plan |
| MM HAZ-11: | Cable Pulling Operations |
| Hydrology and | d Water Quality |
| MM WQ-1: | Conduit Flushing |
| MM WQ-2: | Stormwater Pollution Prevention Plan (SWPPP) |
| Mineral Resou | irces |
| APM MIN-1: | Coordination with California Department of Conservation, Division of Oil, Gas, and Geothermal Resources (DOGGR) |
| Recreation | |
| MM REC-1: | Recreation Public Safety Measures |
| MM REC-2: | Pre- and Post-Construction Inspections |
| Transportation | n/Traffic |
| MM TRANS-1: | Notice to Mariners |
| MM TRANS-2: | Vessel Traffic Corridors |
| Utilities and S | ervice Systems |
| MM WASTE-1: | Recycling Feasibility Analysis |
| Commercial Fi | shing |
| MM CF-1: | Commercial Fishery Constraints |